

Item No	Existing Specifications	Revised
	<p><b>Note</b></p> <p>1) All shutters shall be provided with handles of approved make. Rate quoted shall be inclusive of providing SS locks for shutters (1nos per 1 compartment), SS concealed hinges, channels etc.</p> <p>2) Wherever cabinets are shown as hanging, cost of suspension rail suitable for 130kg with suitable suspension bracket. provided at the rate of 2 Nos per compartment.</p> <p>3) For payment purpose measurement exclusive of legs shall be considered while reckoning front elevation.</p> <p>4) Unless otherwise mentioned Plywood shall be min 19mm thickness BWP ply conforming to IS 710 latest version and green building rating and laminate shall be 1mm thick. Shade of laminate for various areas has been provided in the Technical specification for reference.</p> <p>5) Scope of the work is inclusive all the required materials required for work to complete the work in full specification. In the occurrence of explicitly mentioned progress is already completed at site, the same shall be subjected to deviation as per CI 12 of GCC.</p>	<p><b>Fixed furniture</b></p> <p>(Note 1: All shutters shall be provided with handles of approved make. Rate quoted shall be inclusive of providing SS locks for shutters (1nos per 1 compartment), SS concealed hinges, channels etc.</p> <p>2) Wherever cabinets are shown as hanging, cost of suspension rail suitable for 130kg with suitable suspension bracket. provided at the rate of 2 no.s per compartment.</p> <p>3) For payment purpose measurement exclusive of legs shall be considered while reckoning front elevation.</p>
1	<p>Providing and fixing 600mm deep wardrobe using 19mm thick marine plywood (approved make) in 1mm thick approved make &amp; shade laminate finish for carcass and shutters including required no. of drawer unit, shelves, hanging rod in oval shape using High glass chrome plated steel including supports, SS locks for drawers, shutters etc. complete as per drawings and direction of the Engineer In Charge. (For Apartments) Drawing No. INT - 312, 313, 314, 409, 410, 411, 706, 804, 805. Front elevation shall be measured for payment purpose.</p>	<p>Providing and fixing 600mm overall deep double leaf wardrobe using 19mm thick marine plywood (approved make) in 1mm thick approved make &amp; shade decorative on outer side and 1mm thick white laminate finish for carcass and shutters, Providing &amp; fixing 9mm thick marine plywood backing with approved shade 1mm thick laminate including rear side, white colour laminate in inside face wherever not provided., including One no. of drawer unit, shelves, Hanging rod in oval shape using SS heavy duty support, SS locks for drawers, shutters, 3 numbers of soft closing approved make hinges per shutter, 100mm SS tower bolt, 125mm SS handle per shutter, 6mm wide 2nd class teak wood bidding on all round of each shutter, approved make suitable size telescopic</p>

		<p>25kg weight capacity channels for the drawers with matching knob. The rate shall be inclusive of French spirit polish on the bidding and any additional member to make wardrobe steady and stable etc. complete as per drawings and direction of the Engineer In Charge. (For Apartments) Drawing No. INT - 312, 313, 314, 409, 410, 411, 706, 804, 805. Front elevation shall be measured for payment purpose.</p>
2	<p>Do as above but for completion of balance works of wardrobes in apartments in 3rd floor to 6th floor where partial works have been executed previously. Current scope includes providing all fittings including channels, plywood with laminate finishes for shutter and pasting of approved shade 1mm thick laminate on exterior side and 1mm thick white colour laminate on inside areas wherever pending. Rate quoted shall be inclusive of providing SS locks for the drawers, making provisions for the same in existing shutters, one SS tower bolt for each shutter, hanging rod in oval shape using High glass chrome plated steel including supports etc. for the wardrobes for apartments. Rate quoted shall be lumpsum rate for completion of all the allied works for 16nos of wardrobe of approximately 100 Sqm of area as per the specification. Bidders shall thoroughly inspect the progress at various floor before arriving at their best rate.</p>	<p>Do as above but for completion of balance works including hardware fittings of wardrobes in apartments in 3rd floor to 6th floor where partial works have been executed previously. Current scope includes providing all fittings including channels, plywood with laminate finishes for shutter and pasting of approved shade 1mm thick laminate on exterior side and 1mm thick white colour laminate on inside areas wherever pending. Rate quoted shall be inclusive of providing SS locks for the drawers, making provisions for the same in existing shutters, one SS tower bolt for each shutter, Hanging rod in oval shape using High glass chrome plated steel including supports etc. for the wardrobes for apartments. Rate quoted shall be lumpsum rate for completion of 16 numbers wardrobes all the allied works of wardrobe of approximately 100 Sqm of area as per the specification. Bidders shall thoroughly inspect the progress at various floor before arriving at their best rate. <b>NOTE: The rate of single unit will be derived after divide by 16 to the rate quoted as lump-sum in the item for payment purpose.</b></p>

<p>3</p>	<p>Completion of works for 600mm deep wardrobe for suite room where shutters with 25mmx 25mm has been fabricated and kept at site.</p> <p>Carcass for the wardrobe shall be fabricated using 19mm thick plywood and 1mm thick laminate. Shutters shall be finished with 3 or more coats of melamine polish. Further the rate shall also be inclusive of:</p> <ul style="list-style-type: none"> <li>a) Providing 9mm thick plywood backing with approved shade 1mm thick laminate including rear side, white colour laminate in inside phase wherever not provided.</li> <li>b) Providing and fabricating drawers using 19mm plywood using SS channels of 500mm long with 25kg carrying capacity.</li> <li>c) Providing SS Hanging rods.</li> <li>d) Fixing of already manufactured teakwood shutters.</li> <li>e) Providing 3 or more coats of melamine polish for the shutters.</li> <li>f) Providing and fixing ironmongeries like SS handles 125mm long, Soft closing hinges - 3nos per shutter, SS locks for drawers and shutters etc.</li> </ul> <p>Rate quoted shall be for finishing and placing the wardrobe as per the drawing complete as per drawing drawings and specification and as per instruction of the Engineer In Charge. (For Suit Rooms). Any progress at site shall be considered for deviation as per Cl 12 of the GCC)</p> <p>For payment purpose full and finished wardrobe area in front elevation shall be measured to the nearest 0.01sqm Drawing No. INT - 405, 401</p>	<p>Completion of works for overall 600mm deep wardrobe for suite room and guest room where shutters with 25mmx 25mm and 32mmx 32mm respectively have been fabricated and kept at site.</p> <p>Providing fabricating and fixing Carcass for the wardrobe using 19mm thick marine plywood and 1mm thick white laminate inner surfaces. Shutters and external side shall be finished with melamine polish after required surface preparation. Further the rate shall also be inclusive of</p> <ul style="list-style-type: none"> <li>a) Providing 9mm thick marine plywood backing with approved shade 1mm thick laminate including rear side, white colour laminate in inside phase wherever not provided.</li> <li>b) Providing and fabricating 2 nos of drawers using 19mm plywood using SS channels of required size long with 25kg carrying capacity.</li> <li>c) Providing SS Hanging rods in oval shape with heavy duty SS brackets.</li> <li>d) Fixing of already manufactured teakwood shutters.</li> <li>e) Providing and fixing ironmongeries like SS handles 125mm long, Soft closing hinges - 3nos per shutter, 100mm SS tower bolt, SS locks for drawers and shutters etc.</li> </ul> <p>Rate quoted shall be for finishing and placing the wardrobe as per the drawing complete and specification and as per instruction of the Engineer In Charge. (For Suit Rooms). For payment purpose full and finished wardrobe area in front elevation shall be measured to the nearest 0.01sqm complete as per drawings and Instruction of the Engineer In Charge. Drawing No. INT - 405, 401, 504, 501, 701, 801</p>
----------	---	--

4	<p>Providing and fixing 600 mm deep wardrobe for Guest room as per following specification:</p> <p>a) Carcass including drawers shall be providing with 19mm thick plywood with laminate finish (including rear side). Inside area shall be provided with white colour 1mm laminate.</p> <p>b) Fixing of teakwood shutter 32mmx32mm supplied by the Bank.</p> <p>Rate quoted shall be inclusive of providing 3 or more coats of melamine polish for the shutters and providing ironmongeries and fittings like SS channels of 500mm long with 25kg carrying capacity for drawers, SS handles 125mm thick, Soft closing hinges - 3nos per shutter, SS locks for drawers and shutters, SS hanging rods etc. complete as per drawings and Instruction of the Engineer In Charge. Drawing No. INT - 504, 501, 701, 801</p>	<p>Completion of works for overall 600mm deep wardrobe for suite room and guest room where shutters with 25mmx 25mm and 32mmx 32mm respectively have been fabricated and kept at site.</p> <p>Providing fabricating and fixing Carcass for the wardrobe using 19mm thick marine plywood and 1mm thick white laminate inner surfaces. Shutters and external side shall be finished with melamine polish after required surface preparation. Further the rate shall also be inclusive of</p> <p>a) Providing 9mm thick marine plywood backing with approved shade 1mm thick laminate including rear side, white colour laminate in inside phase wherever not provided.</p> <p>b) Providing and fabricating 2 nos of drawers using 19mm plywood using SS channels of required size long with 25kg carrying capacity.</p> <p>c) Providing SS Hanging rods in oval shape with heavy duty SS brackets.</p> <p>d) Fixing of already manufactured teakwood shutters.</p> <p>e) Providing and fixing ironmongeries like SS handles 125mm long, Soft closing hinges - 3nos per shutter, 100mm SS tower bolt, SS locks for drawers and shutters etc.</p> <p>Rate quoted shall be for finishing and placing the wardrobe as per the drawing complete and specification and as per instruction of the Engineer In Charge. (For Suit Rooms). For payment purpose full and finished wardrobe area in front elevation shall be measured to the nearest 0.01sqm complete as per drawings and Instruction of the Engineer In Charge. Drawing No. INT - 405, 401, 504, 501, 701, 801</p>
5	<p>Providing and fixing Toilet Doors as per the following Specifications.19mm thick Marine Plywood fixed both sides with 1 mm thick approved shade Laminate fixed to the Laminated panels with all necessary Hardware like - hinges, S.S. 'H' Handles 450mm long, Tower Bolts, Latches with Vacant / Engage sign all approved makes as per detailed drawings and instruction of the Engineer In</p>	<p>Providing fabricating and fixing 19mm thick Marine Plywood toilet door with both sides with 1 mm thick approved Laminate fixed to the Laminated panels with all necessary Hardware like - 125mm 3nos SS heavy duty hinges, S.S. 'H' Handles 450mm long, 100mm SS Tower Bolts, Latches with Vacant / Engage sign all approved makes as per detailed drawings and instruction of the Engineer In Charge. The rate</p>

	Charge. The rate shall include for supplying and fixing 1 No. Twin Robe hook per door as per approved sample. Drawing No. AR WD 61,62,63,64,65, INT - 311, 408, 504, 708	shall include for supplying and fixing 1 No. Twin Robe hook per door as per approved sample. Drawing No. AR WD 61,62,63,64,65, INT - 311
6	Providing and fixing fixed panels for the toilet as per the following Specifications.19mm thick Marine Plywood fixed both sides with 1 mm thick approved shade Laminate fixed to the Laminated panels. The fixed panels shall have provision for hiding the switch box module, PVC extruded sections along the plywood edges etc complete as per specification and instruction. Drawing No. AR WD 61,62,63,64,65, INT - 311, 408, 504, 708	Providing and fixing fixed panels for the toilet as per the following Specifications.19mm thick Marine Plywood fixed both sides with 1 mm thick Silver Laminate fixed to the Laminated panels. The fixed panels shall have provision for hiding the switch box module, PVC extruded sections along the plywood edges etc. complete as per specification and instruction. Drawing No. AR WD 61,62,63,64,65, INT - 311
7	Providing and fixing storage units 400 mm deep of any height and varying lengths and heights as per drawings made out of 19mm thick marine grade plywood of approved make top, bottom, sides, sliding / openable shutters and required number of shelves and 8mm marine plywood back with necessary beading, hardware such as Locks, Hinges, Handles etc. All the works shall be carried out as per detailed drawings and instruction of the Engineer In Charge. The rate shall include for providing drawers of required size & nos as per drawings & the drawers shall be fixed with heavy duty telescopic sliding channels of approved make. All Exposed surfaces of the unit shall be finished with 1 mm thick laminate of approved make & shade and internal portion shall be finished with 2 or more coats of french polish. Note: Area in front elevation shall be measured for payment. MS powder coated legs wherever indicated shall be part of furniture and the same shall not separately measured. Drawing No. INT - 103, 201, 301, 306,307, 308, 108, 110, 111, 210, 211, 212, 213, 214	Providing and Fixing storage units 400 mm deep of any height and varying lengths as per drawings made out of 19mm thick marine grade plywood of approved make top, bottom, sides, sliding/ openable shutters and required number of intermediate shelves, including One no. of drawer unit (in openable units), shelves based on the height of the unit and 8mm marine plywood back with necessary beading, hardware such as Locks-01 concealed/storage unit lock for sliding/openable shutters, 125 mm concealed/exposed type SS handles, approved make suitable size telescopic 25kg weight capacity channels for the drawers with matching knob etc. All the works shall be carried out as per detail drawings and instruction of the Engineer In Charge. All Exposed surfaces of the unit shall be finished with 1 mm thick decorative laminate of approved make & shade and internal portion shall be finished with 2 or more coats of french polish. Note: Area in front elevation without legs shall be measured for payment. The rate shall be including of repairing and re-powder coating of exiting 32mm x 32 mm MS legs as per site condition. Drawing No. INT - 103, 201, 301, 306,307, 308, 108, 110, 111, 210, 211, 212, 213, 214

<p>8</p>	<p>Same as item no.7 for completion of full finishing of storage unit where in following works are to be completed:</p> <p>a)2 or more coat of French polish of inside cabins including shutter.</p> <p>b)Rear laminate to be provided.</p> <p>c) Procuring and fixing SS locks of approved makes with SS keys.</p> <p>d) Fixing of hinges and handles as supplied by the Bank. etc</p> <p>e) Providing 150mm high legs in 32mmx32mm heavy thickness powder coated wherever indicated.</p> <p>Rate shall be inclusive of necessary correction of bends/alignment of shutters, placing/hanging the furniture at identified locations using approved fittings, providing screws required for hinges and handles, pins for supporting rack etc. complete as per the direction of the Bank.</p> <p>For measurement purpose front elevation shall measure in nearest 0.01 sqm for payment purpose</p>	<p>Do as item no.7 for completion of full finishing of storage unit where in following works are to be completed with 2 or more coat of french polish of inside storage units including shutter.</p> <p>To complete the balance work following works shall be carried:-</p> <p>a) Providing &amp; fixing 1mm thick laminate on the back exposed side of the unit.</p> <p>c) Procuring and fixing SS concealed/exposed lock to the shutters of approved makes with SS keys.</p> <p>d) Fixing of hinges and handles as supplied by the Bank etc</p> <p>e) Providing, welding and fixing 150mm high legs in 32mmx32mmx1.63 mm thick powder coated wherever indicated.</p> <p>Rate shall be inclusive of necessary correction of bends/alignment of shutters, placing/hanging the furniture at identified locations using approved fittings, providing screws required for hinges and handles, pins for supporting rack etc. complete as per the direction of the Bank.</p> <p>For measurement purpose front elevation shall measure in nearest 0.01 sqm for payment purpose.</p>
<p>9</p>	<p>Do as per item no. 7 for completion of full finishing of storage unit with sliding shutters where in following works are to be completed:</p> <p>a) Replacement of local sliding rail already provided with the sliding channel, rollers and accessories from approved make and quality.</p> <p>b) Providing new sliding shutter with 19mm thick IS 710 plywood with laminate finish on outside and French polish of inside cabins including rear shutter area</p> <p>b) Laminate to be provided on rear area of the furniture.</p> <p>c) Fixing of hinges and handles as supplied by the Bank etc.</p> <p>Rate shall be inclusive of necessary correction of bends/alignment of shutters, placing of furniture at identified locations, providing screws required for hinges and handles, pins for supporting rack etc. complete as per the direction of the Bank.</p> <p>For measurement purpose front elevation shall</p>	<p>Do as per item no. 7 for completion of full finishing of storage unit with sliding shutters where in following works are to be completed</p> <p>a) Providing &amp; fixing heavy duty required size 25 kg weight capacity sliding channel, sliding rail, rollers and other accessories after removal of existing of same local hardware fittings.</p> <p>b) Providing &amp; fixing in position new sliding shutter with 19mm thick IS 710 Marine approved make plywood with 1mm thick decorative laminate finish on outside.</p> <p>French polish of inside cabins including rear shutter area.</p> <p>b) Providing &amp; fixing 1mm thick Laminate on rear area of the unit.</p> <p>c) Fixing of hinges and handles as supplied by the Bank. etc</p> <p>Rate shall be inclusive of necessary correction of bends/alignment of shutters, placing of furniture at identified locations, providing screws required for hinges and handles, pins for</p>

	measure in nearest 0.01 sqm for payment purpose.	supporting rack etc. complete as per the direction of the Bank. For measurement purpose front elevation shall measure in nearest 0.01 sqm for payment purpose.
10	Do - as above item no. 9 but finished with 4mm thick veneer of approved make & shade for storage unit with sliding unit (except exposed back face which is to be finished with laminate) finished with 3 or more coats of melamine polish for exposed area etc. complete as per drawings and Instruction of the Engineer In Charge. Note: Area in front elevation shall be measured for payment. Drawing No. INT - 112, 113, 207 A, 207 B, 209	Do as above item no. 7 but finished with 4mm thick veneer of approved make & shade for storage unit with sliding unit (except exposed back face which is to be finished with 1 mm thick laminate) finished with of melamine polish after required surface preparation for exposed area etc. complete as per drawings and Instruction of the Engineer In Charge. Note: Area in front elevation shall be measured for payment. Drawing No. INT - 112, 113, 207 A, 207 B, 209
11	Do as above item no 8 for completion of full finishing of storage unit with openable shutter provided with veneer finish where in following works are to be completed a) French polish of inside cabins including shutter.b) Rear laminate to be providedc) 3 more coats of melamine polish on exposed veneer surfacesd) Fixing of hinges and handles as supplied by the Bank.etc Rate shall be inclusive of necessary correction of bends/alignment of shutters, placing/hanging the furniture at identified locations using approved fittings, providing screws required for hinges and handles,pins for supporting rack etc. complete as per the direction of the Bank.For measurement purpose front elevation shall measured in nearest 0.01 sqm for payment purpose	Do as above item no 7 for completion of full finishing of storage unit with openable shutter provided with veneer finish where in following works are to be completed a) Providing & applying French polish of inside surfaces of the unit including shutter. b) Providing & fixing 1mm thick lamination of the back side of unit. c) Providing and applying melamine polish on exposed veneer surfaces with required surface preparation. d) Fixing of hinges and handles as supplied by the Bank. etc Rate shall be inclusive of necessary correction of bends/alignment of shutters, placing/hanging the furniture at identified locations using approved fittings, providing screws required for hinges and handles,pins for supporting rack etc. complete as per the direction of the Bank. For measurement purpose front elevation shall measured in nearest 0.01 sqm for payment purpose.

12	<p>Providing and fixing curved furniture in oval room using 19mm plywood with veneer 4mm thickness of approved shade and finished with 3 or more coat of melamine polish, inside area shall be provided french polish in approved shade, Drawers shall be fixed using approved quality fittings and shall be hanging as shown in the drawing etc. complete as per specification and as instructed Ref Dwg( INT 113)</p>	<p>Providing and fixing marine IS 710 plywood as table top in curve shape over the existing MS undercarriage in oval room with required number and size SS screws. Providing and fixing 4mm thick approved make, shade and finished veneer over the ply top with approved make adhesive. The rate shall be inclusive of providing&amp; fixing trapezium shape 2nd class teak wood moulding all-round of the table of size 15 mm X 50mm for double thickness at the edges. Providing and applying melamine polish on the veneer and moulding after required surface preparation and inside area shall be finished with french polish in approved shade, Drawers shall be fixed using approved quality fittings and shall be hanging as shown in the drawing etc. complete as per specification and as instructed Ref Dwg(INT 113)</p>
13	<p>Do - as item no. 7 but for side unit in Board Room with M. S. under carriage frame with proper fixing arrangement in approved manner. The frame will also support the 6mm thick mirror on backing on 12mm thick marine ply. Rate shall include 10 mm thick glass on top, SS locks for each compartment, SS soft closing channels, soft closing hinges etc. complete as per drawings and instruction of the Engineer In Charge. Drawing No. INT - 101, 201, 114, 204 Rate quoted shall be in lumpsum for fabricating the unit</p>	<p>Do as item no. 7 but for side unit in Board Room with M. S. under carriage frame with proper fixing arrangement in approved manner. The frame will also support the 6mm thick mirror on backing on 12mm thick marine ply. Rate shall include 10 mm thick glass on top, SS locks for each compartment, SS soft closing channels, soft closing hinges etc. complete as per drawings and instruction of the Engineer In Charge. Drawing No. INT - 101, 201, 114, 204 Rate quoted shall be in lumpsum for fabricating the unit.</p>
14	<p>Providing and fixing open bookshelves of 400 mm deep on one side linearly tapered to zero width on the other side in the Director's cabin. Each rack shall be of made of 19mm thick plywood suitable fixed to 4mm Veneer with melamine polish finish and has to be suitable fixed to the wall. Rate quoted shall be also be inclusive of providing and fixing heavy quality MS support system of 20mm square with minimum 2mm thickness, finished with 50micron powder coating, and its fixing using flanges and dash fasteners, welding, buffing, grinding etc. Bidders has to quote for the cost of fabrication and fixing of the unit in complete as shown in drawing. Drawing No. INT - 207 A, 207 B</p>	<p>Providing, fabricating, welding &amp; fixing open bookshelves frame by using 20mm x20mm x2mm thick MS hollow square tube. The frame for open book shelves of 400 mm overall deep on one side linearly tapered to 150 mm width on the other side in the Director's cabin. The fabricated frame shall be powder coated in approved colour with minimum 50 micron thickness. Providing and fixing of 19mm thick IS 710 Marine plywood over the M S frame with required number and size screws and finished with 4mm thick approved make, shade and pattern Veneer with approved make adhesive. The surface shall be finished with melamine polish finish after required surface preparation. The rate shall be inclusive of suitably fixed to</p>



		the wall. Drawing No. INT - 207 A, 207 B
15	<p>Completion of following works in the movable pedestals in laminate finish and making ready the same for usage:</p> <p>a) Providing French polish to the inside areas  b) Providing Heavy duty rollers for the pedestals- 4nos per pedestals  c) Providing rear laminate of 1 mm thickness in approved shade  d) Providing all remaining fittings (which ever is missing) including 1no SS handle of approved make.  e) Placing the same at different locations etc.</p> <p>Bidders shall quote lumpsum rate for making ready a total no. of 51nos pedestals already available at the site as per the approved drawings and as per instruction of the Bank</p>	<p>Completion of following works in the movable pedestals in laminate finish and making ready the same for usage.</p> <p>a) Providing and applying French polish to the inside surfaces.  b) Providing and fixing Heavy duty rollers for the pedestals- 4nos per pedestals  c) Providing and fixing 1 mm thick lamination of approved make and shade on the back side of the pedestals.  d) Providing and fixing all remaining fittings(whichever is missing) including 1no 125 mm SS handle, 01 lock approved make lock per pedestal.  e) Placing the same at different locations etc.  f) fixing 32mm dia heavy duty SS pipe legs.</p> <p>Bidders shall quote lumpsum for 51 pedestals rate for making ready pedestals already available at the site as per the approved drawings and as per instruction of the Bank <b>NOTE: The rate of single unit will be derived after divide by 51 to the rate quoted as lum-sump in the item for payment purpose.</b></p>
16	<p>do as item no. 15 but for movable pedestals in veneer finish. Rear area shall be completed with veneer finish and rate quoted shall be also be inclusive of providing 3 or more coats of melamine finish for the entire pedestals. Bidders shall quote lumpsum rate for making ready a total no. of 5 pedestals already available at the site as per the approved drawings and as per instruction of the Bank</p>	<p>do as item no. 15 but for movable pedestals finish with 4mm thick approved make, shade and pattern veneer shall be finished with melamine polish for the entire pedestals after required surface preparation. Bidders shall quote lumpsum rate for 5 pedestals for making ready pedestals already available at the site as per the approved drawings and as per instruction of the Bank.<b>NOTE: The rate of single unit will be derived after divide by 5 to the rate quoted as lum-sump in the item for payment purpose.</b></p>
17	<p>Providing and Fixing 12mm thick pin-up board paneling with approved fabric above workstation table top level, mounted on partition in approved manner complete as per drawings and Instruction of the Engineer In Charge. Drawing No. INT - 108, 110, 111, 304, 306, 307, 308, 212, 213, 214. Basic rate of fabric : 400/Rm</p>	<p>Providing and Fixing 12mm thick pin-up board paneling with approved fabric above workstation table top level, mounted on partition in approved manner complete as per drawings and Instruction of the Engineer In Charge. Drawing No. INT - 108, 110, 111, 304, 306, 307, 308, 212, 213, 214. Basic rate of fabric : 400/Rm</p>

18	Providing and Fixing Wooden skirting of size 12 mm x 75 mm (on the outside areas of cabins made with calcium silicate board) Teakwood supplied by the Bank . Skirting shall be suitable finished with 3 or more coats of melamine polish, necessary screws, adhesives, joint complete as per drawings and Instruction of the Engineer In Charge. Drawing No. INT - 03, 103, 203, 303	Providing and Fixing Wooden skirting of size 12 mm x 75 mm (on the outside areas of cabins made with calcium silicate board) Teakwood supplied by the Bank . Skirting shall be suitable finished with melamine polish after necessary surface preparation, necessary screws, adhesives, joint complete as per drawings and Instruction of the Engineer In Charge. Drawing No. INT - 03, 103, 203, 303
19	Providing and fixing partition with in Guest room of 32mm thick with 19mm thick plywood with finished with 4mm thick veneer and melamine polish including side ledges of 250mm wide on both sides made of 19mm plywood with veneer and melamine polish as indicated in the drawing. Rate shall be inclusive of providing chasing for hiding the cables and provision for concealment of switch boxes, provisions for fire fighting sprinkler, light point etc. For payment purpose front area of partition only (exclusive of opening and frame) to nearest 0.01 sqm shall be measured. Drawing No. INT - 404, 405	Providing and fixing double skin partition with in Guest room - 32mm thick wooden partition shall be fabricated with 16 x 25 mm thick 2nd class teak wooden batten frame maximum 600 mm C/C spacing both side and 8 mm thick marine ply on both the faces. The surface shall be finished with 4mm thick veneer and Melamine polish including side ledges of 250mm wide on both sides made of 19mm plywood with veneer and melamine polish. Rate shall be inclusive of providing chasing for hiding the cables and provision for switch boxes, provisions for fire fighting sprinkler, light point etc. For payment purpose front area of partition only (exclusive of opening and frame) to nearest 0.01 sqm shall be measured. Drawing No. INT - 504
20	Supplying and Fixing Magnetic white boards in Staff area and cabins including accessories like, eraser, markers, necessary frame work etc. complete as per drawings and Instruction of the Engineer In Charge. Drawing No. INT - 108, 110, 111, 304, 306, 307, 308, 212, 213,214	Supplying and Fixing Magnetic white boards in Staff area and cabins including accessories like, eraser, markers, necessary frame work etc. complete as per drawings and Instruction of the Engineer In Charge. Drawing No. INT - 108, 110, 111, 304, 306, 307, 308, 212, 213,214
21	Providing and fixing stainless steel soft closing spring hinges at 0 degree hinges (hydraulic type) of approved make/brand to cupboard shutters with full threaded steel screws including making necessary recess in board and finished etc. complete as per direction of Engineer-in-charge.	Providing and fixing stainless steel soft closing spring hinges at 0 degree hinges (hydraulic type) of approved make/brand to cupboard shutters with full threaded steel screws including making necessary recess in board and finished etc. complete as per direction of Engineer-in-charge.
22	Providing and fixing stainless steel soft closing heavy type telescopic drawer channels of approved make 500 mm long with screws etc. complete as per directions of Engineer- in-charge	Providing and fixing 500 mm long soft closing heavy type approved make telescopic drawer channels with screws etc. complete as per directions of Engineer- in-charge

23	<p>Completion of reed paneling work in oval room as per following specification</p> <p>a) Rectification of reeds which are not in line.</p> <p>b) On rectification the reed patty shall be finished with 3 coat of melamine polish of approved shade.</p> <p>Rate quoted shall be in lumpsum for execution of entire work of approximate area 120Sqm. including movable scaffolding suitable for working at double heights and any other material required for complete finishing as per drawing and instruction . Drawing No. INT - 112, 101 AC - 01.</p>	<p>Completion of reed paneling work in oval room as per following specification</p> <p>a) Rectification of reeds which are not in line.</p> <p>b) Reed patty shall be finished with melamine polish after required surface preparation.</p> <p>c) All materials to be provided by the Bank and the part materials installed shall be thoroughly cleaned.</p> <p>Rate quoted shall be in lumpsum for execution of entire work of approximate area 120Sqm. including movable scaffolding suitable for working at double heights for finishing as per drawing and instruction . Drawing No. INT - 112, 101 AC - 01.</p>
24	<p>Rectification and completion of splay fabric paneling work in oval room as per the drawing and specification:</p> <p>a) GI frame already provided along the periphery shall be inspected and necessary rectification shall be done by providing and fixing sections matching with the already provided.</p> <p>b) Providing and replacing old and dilapidated, wherever required as per the direction of the Bank's Engineer.</p> <p>c) Providing and fixing the 50mm thick 1000 GSM acoustic material of NRC value 0.92 matching with the already provided mineral/glass wool material.</p> <p>d) Fixing of Bank supplied wood wool board on fixed on 75x12mm ply patty complete as per design, drawing. Cost of procurement of plywood needs to be considered.</p> <p>e) Wood wool board shall be finished with fabric on gripper system as per specification.</p> <p>f) Bank shall provide the splay fabric required for fixing in the gripper system. Rate shall be inclusive of mounting the same on the wool board without wrinkles and folds using highly skilled technique without damaging the finish of the fabric.</p> <p>g) Any insufficient fabric shall be procured at a basic rate of Rs. 600/Rm, which shall be paid separately.</p> <p>h) Rate quoted shall be inclusive of movable double scaffolding required for successful</p>	<p>Rectification and completion of splay fabric paneling work in oval room as per the drawing and specification.</p> <p>a) GI frame already provided along the periphery shall be inspected and rectified using sections matching with the sections provided shall be procured and fixed( for which no additional payment shall be considered and the quoted rate shall be inclusive of the same)</p> <p>b) Old and dilapidated 50mm thick 1000 GSM acoustic material shall be replaced and provided with matching materials.</p> <p>c) Rate quoted shall be inclusive of providing the acoustic material wherever not provided of NRC value 0.92 matching with the already provided material</p> <p>d) Fixing of Bank supplied wood wool board on fixed on 75x12mm ply patty complete as per design, drawing. Cost of procurement of plywood needs to be considered.</p> <p>e) Wood wool board shall be finished with fabric on gripper system as per specification.</p> <p>f) Bank shall provide the splay fabric required for fixing in the gripper system without wrinkles and folds using highly skilled technique without damaging the finish of the fabric. Any insufficient fabric shall be procured at a basic rate of Rs. 600/Rm, which shall be paid separately.</p> <p>g) Rate quoted shall be inclusive of movable double scaffolding.</p> <p>h) All materials to be provided by the Bank and</p>

	<p>completion of the work.</p> <p>i) All materials to be provided by the Bank and the part materials installed shall be inspected and thoroughly cleaned before put into use. Rate quoted shall be in lumpsum for execution of entire work of approximate area 150.00 Sqm and protection of the work till handing over as per drawing and instruction. Bidders shall thoroughly inspect the site and understand the site requirement before quoting.</p>	<p>the part materials installed shall be thoroughly cleaned.</p> <p>Drawing No. INT - 112, 101 AC - 01</p> <p>Rate quoted shall be in lumpsum for execution of entire work of approximate area 150.00 Sqm and protection of the work till handing over as per drawing and instruction. Bidders shall thoroughly inspect the site and understand the site requirement before quoting</p>
--	--	---